

Amrapali Sapphire Phase-2 AOA

Sector-45, Noida
Sports Committee

Tender Notice – Development of Pickleball Courts

Amrapali Sapphire Phase-2 AOA, through the Sports Committee, invites **sealed quotations** from experienced and qualified vendors/contractors for the development of two (2) pickleball courts within the society premises.

The concrete base for the courts is already available at the site.

Scope of Work

- Cleaning and preparation of the existing concrete floor, including minor crack repairs if required.
- Application of outdoor acrylic sports coating with anti-skid finish suitable for pickleball courts.
- Standard pickleball court line marking for two courts as per official dimensions.
- Supply and installation of two regulation pickleball nets with poles and tensioning system.
- Installation of high-quality perimeter mesh fencing surrounding both courts


Mesh Fencing Specifications

- ✓ Heavy-duty mesh fencing around both courts with common perimeter enclosure.
 - ✓ Minimum fencing height: 10 feet.
 - ✓ MS Main poles 3 inch * 3 inch , type B
 - ✓ Connecting poles & beams -MS , 2 INCH * 2 INCH , TYPE B , TOP CENTER BOTTOM
 - ✓ All poles to be painted.
 - ✓ One access gate with locking provision for controlled entry.
 - ✓ All fittings, clamps, tension wires, and accessories required for proper installation to be included.
-
- Supply and installation of LED sports lighting suitable for evening play.
 - Completion of all associated civil, electrical, and installation work required for proper functioning of the courts.



Bill of Quantities (BOQ)/ PRICE BID

S.No.	Description of Work	Unit	Qty	Rate (INR)	Price	Tax	Amount (INR)
1	Acrylic layer with Fiber Mesh 2 LAYER Concrete PRIMER 2 layers resurface 2-layer cushioning 2-layer acrylic paints Minimum 8+1 layers 2 layers for Line Markings for final Game	SQFT	3600 (60 x 60)				
2	MS Poles Type B, Fixed Poles with Nets - powder coated	SETS	2				
3	MS fencing 10 Feet height 3inch x 3 inch -Main Poles 8 Nos Type B Connecting Poles and Beams Top, bottom and center 2-inch x 2-inch Type B Paint 1 layer MS primer 2-layer MS paint	Lot	1				
4	Fencing Mesh - GI, 3mm, 2inch x 2 inches Paint - 1 layer MS primer 2-layer MS paint	Lot	1				
5	Light Poles extended 3 feet above main poles 50 W Flood light 4 Nos per Pole (Havells / Philips) 3 core wiring up to Junction Box (Poly cab/ KEI/ Avocab) covered in flexible plastic hose	Nos	8				



	for weather protection Junction Box with MCB						
6	Floor Preparation with epoxy and silicon Polymer						
7	Transportation						
8	Miscellaneous Item						

General Terms and Conditions

- Contractors are advised to inspect the site before submitting their quotation.
- The quoted rates must include all labour, materials, equipment, transportation, and applicable taxes.
- The work should be completed within 30 days from the date of issue of the work order.
- Payment will be released after inspection and approval by the Sports Committee / AOA.
- The contractor shall be responsible for the safety of materials and existing infrastructure during the execution of the work.
- BOM reserves the right to cancel this tender anytime without providing any reason / justification.

Submission Details

Maintenance Office
Amrapali Sapphire Phase-2
Sector-45, Noida

VIVEK KUMAR - 8090291157

YASHVARDHAN KASHYAP - 9742212206

LaSst Date for Submission: 16th may 2026 , 11:30 AM

Tender Opening Date: 16th May 2026 , 12:30 PM

Issued By:
Sports Committee
Amrapali Sapphire Phase-2 AOA

Signature: _____

